

MERIDIAN CAMPUS – DYSONS ROAD SITE

As noted in the full report, Meridian Campus Dysons Road site comprises a number of building including the main school building (original Church Hall) and part of the Church building which have both been adapted for use as an educational facilities, along with 3 No. modular buildings to the rear of the site.

The site is generally accessible, with the exception of some staff areas in the main school building. Due to the limitations of the existing building structure, it would almost certainly not be viable to carry out all adaptations necessary to provide full wheelchair access to all areas of this buildings however recent modifications have been carried out to improve layout and circulation. The following recommendation details improvements that can be undertaken:

Area	Issue	Recommendation
Hygiene Room	Non contrast handrails and toilet seat.	Replace with suitable contrasting fittings.

MERIDIAN CAMPUS - SPRINGFIELD ROAD SITE

Meridian Campus – Springfield Road site is fully accessible having recently had a new lift installed providing access to the first floor areas.

Recommendations for further works that could be undertaken are below:

Area	Issue	Recommendation
First Floor	No DDA toilet	Install DDA toilet to cleaners room

HASELBURY CAMPUS

Haselbury Campus; completion of the final phase of refurbishment and new build works has provided an accessible site.

LEARNING FOR LIFE CAMPUS

As noted in the report, Learning for Life Campus is located on a sloping site, where there are numerous steps in corridors and at access points to overcome the difference in levels.

It would almost certainly not be financially viable to carry out all adaptations necessary to provide a fully accessible site, however significant works have been / are being undertaken to address accessibility issues as far as possible. The works include widening of door opening, installation of internal wheelchair platform lifts and formation of a new lower ground floor extension with level access and accessible WC facilities.

We have therefore broken down our recommendations for further works that could be undertaken, or further feasibility investigations undertaken:

Area	Issue	Recommendation
Main front entrance	Stepped access up from reception area.	Not possible to provide level access via the front main entrance. Consider use of a platform lift to main corridor to enable level access to the reception and staff areas.

HORIZON CAMPUS – PONDERS END COLLEGE

Horizon campus – Ponder End College; major refurbishment works have recently completed which now provides an accessible site.

HORIZON CAMPUS – ST. MARY'S

As noted in the full report, Horizon Campus St. Marys was previously a church centre which has been modified. The buildings have been linked and extended, and internal alterations undertaken to make the accommodation suitable for use as an education facility.

Due to the limitations of the existing building structure, it would almost certainly not be viable to carry out all adaptations necessary to provide full wheelchair access to all areas and levels of the buildings. The following recommendations are made detailing the areas where improvements can be undertaken, or further feasibility investigations carried out:

Area	Issue	Recommendation
Secondary Entrance	Double Doors	Install fully automated doors
Induction Loop	If no induction loop.	Install induction loop to front entrance area and classroom/hall.
Hygiene Room	No handrails or shower seat	Install handrails and shower seat.
External Area	Level access into play area directly from corridor	Install ramp to rear door adjacent to kitchenette.

ASU CYPRUS ROAD

ASU Cyprus Road has been substantially renovated from a domestic property into an education establishment.

It would almost certainly not be financially viable to carry out all adaptations necessary to provide full wheelchair access to all areas and levels of the buildings.

We have therefore broken down our recommendations for works that could be undertaken, or further feasibility investigations undertaken, as well as a high level budget estimate against each item below:

Area	Issue	Recommendation
WC's	No ambulant provision to ground and first floor WCs.	Install handrails, and upgrade walls for robust fixing.
Hygiene room	Minor issues as detailed in full report.	Provide contrast toilet seat, install grab rail and folding chair in shower area, adapt WHB.
External Areas	Poor lighting.	Install additional external lighting.